

 $^{\star}$  NOTES: ALL DDCVA'S SHALL HAVE TOUCH-READ (TRPL) UNITS INSTALLED BY DEVELOPER/CONTRACTOR.

INSTALL LOCKING VALVE BOX LID FOR VALVE CONTROLLING SUPPLY LINE TO DDCVA.

OUTSIDE ACCESS DOOR TO FIRE DEVICE MUST BE PROVIDED.

BYPASS METER SHALL BE 5/8" X 3/4" SENSUS SR-II MODEL WITH ELECTRONIC

REGISTER & PLUG-IN CONNECTORS.

\* PROVIDE DOOR FOR DIRECT ENTRY FROM OUTSIDE OF BUILDING. \*

## DOUBLE DETECTOR CHECK VALVE ASSY. INSIDE BUILDING W / PIV & FDC

NTS

REVISION DATE
10/19/07
SED
CHECKED
TDK
DISTRICT APPROVED
TDK
PLOTTING SCALE
NTS
F:\DWGS\DETAILS-2004\HWD-035
DATE APPROVED
10/19/07



35